

Demonstration Data

Office 300 Broadstone Mill
Stockport
SK5 7DL
Tel: 0151 558 1964
Email: info@contractcontroller.co.uk



Mr J Severn
The New Clothing Company
Unit 17
Manchester Way
Manchester
MA1 6YR

Quotation No. 2804-R1

Date: 17/10/2024
Estimator:
Customer's Tel'.: 0161 4564 4565

Customer's E-mail: John.severn,@Contractcontroller.co.uk

Dear John,
Re: New Ferry

We thank you for your enquiry in respect of the above and have pleasure in submitting our quotation as follows and in accordance with the attached priced schedule:

Site Address:
535 New Chester Road
New Ferry
Town
CH42 1TF

Drawings / Scope of works that this Quotation is to be read in conjunction with:
220052-Tailored, qr-code (1), qr-code (1), Project Manager, PowerScan-9600-image2

Form Of Contract: Standard Terms

Total Quotation Value: £ 11,295.84
For (Excluding VAT)
Quotation Valid For 30 Days

We trust that the enclosed meets with your approval and look forward to hearing from you in due course.
Assuring you of our best service and attention at all times.

Yours faithfully,

For and on behalf of:
Demonstration Data



Quotation No. : 2804-R1 For - The New Clothing Company

New Ferry

Bill Schedule

Item Reference:
To remove & dispose of Existing stud partitions to rear area.

Qty	Unit	Rate	Total
1	Sum	569.63	569.63

Item Reference:
To remove & dispose of Existing carpet tiles to all rear areas.

Qty	Unit	Rate	Total
1	Sum	284.82	284.82

Item Reference:
To Remove & dispose of existing suspended ceiling to rear areas.
(To be carried out in conjunction with the removal of flooring.)

Qty	Unit	Rate	Total
1	Sum	261.42	261.42

Item Reference:
Supply & install 60 minute fire rated stud partition using metal studs at 600mm centres with 2 layers of 12.5mm standard plasterboard to each side.
Tape & Jointed & ready for decoration.

Qty	Unit	Rate	Total
45.52	M2	63.65	2,897.35

Item Reference:
Supply and Install door & frame to prepared opening by others.
2040 x 826 x 44mm
Paint grade complete with 5 lever lock and overhead door closer.
Includes 300 x 300 clear vision panel.
Excludes architraves.

Qty	Unit	Rate	Total
1	Each	431.38	431.38

Item Reference:
Supply & install Reception desk:
Constructed from 18mm MDF with lamite finis to external faces. Spray to internal.

Qty	Unit	Rate	Total
1	Sum	2,323.91	2,323.91

Item Reference:
3 Drawer Pedestal - on casters
430mm wide x 670mm x 600mm deep
Constructed from 18mm MDF
(Required Finishes To Be Applied at Bill Level)
Top drawer to be lockable.

Qty	Unit	Rate	Total
1	Sum	2,323.91	2,323.91

Quotation No. : 2804-R1 For - The New Clothing Company

New Ferry

Bill Schedule

Item Reference:
Revision 01:
Additional Stud Partitioning to rear area.
Supply & install 60 minute fire rated stud partition using metal studs at 600mm centres with 2 layers of 12.5mm standard plasterboard to each side.
Tape & Jointed & ready for decoration.

	Qty	Unit	Rate	Total
	5.45	M2	63.65	346.89
: To Collection Page (GBP)				11,295.84

Quotation No. : 2804-R1 For - The New Clothing Company

New Ferry

Bill Schedule

Bill Collection Page

	<i>Bill Page</i>				<i>Total</i>
					11,295.84
	Total Value Of All Pages				
			11,295.84		
	Grand Total	(GBP)	11,295.84		



Terms & Conditions

General:

All prices quoted are subject to VAT at the current rate.

Payment Terms:

For all payments that are not monthly based, 50% on order with balance payable 28 days following installation.